



H-35 INVENTORY

DRAWWORKS:

Ideco Single Drum H-35 New Drum Bearings, Brakes 2009, Kobelt Disk Aux Brake 48 Inch, 1 Inch Drill Line, 3406 Cat Engine 425 HP 5510 Hrs, Transmission Allison 6 Speed; Rebuilt by Stewart Stevenson 2008, Foster Makeup and Breakout Catheads, Mounted on 5 Axle Carrier

MAST & SUBSTRUCTURE:

Ideco 96 ft. Telescoping Double Rated at 180,000# Static Hook Load with 6 Lines, 3 Stage Hydraulic Raising Ram, Racking Board Capacity 5500 ft. with 4" Drill Pipe, Ladder, Guy Wires, Fluorescent Lights, 4" Stand Pipe with 4 and 2 Inch Mud Wonder Gate Valves, Mud Pressure Gauge, Ideco Substructure 11 xt kb, 2 Rosier Pull Down Winches ; for extended length horizontal drilling at shallow depths, 2 Rosier Catline Winches

MUD PUMPS:

Gardner Denver 200 FXN 500 HP 350 GPM Duplex with 5-1/2" Liners, 14" Stroke p/b Cat 3412 1378 hrs. since Major Overhaul, Skid Load 9' x 28'

ROTARY EQUIPMENT:

Ideco 22" Rotary Table with Varco Split Master Bushing Driven by Drawworks Draw Line
Emsco L200 200 Ton swivel - overhauled in 2008

TRAVELING EQUIPMENT:

McKissick Traveling Block 100 Ton 1" Line Ser. #492
Hydra Hook Ser. # 10652
BJ Elevator Bails

HANDLING TOOLS:

BJ Type C Manual Tong
Foster Tong 4-1/2 - 7 Inch Casing - p/b Rig Hydraulics
Den Con 4" Drill Pipe 150 Ton Elevators
BJ 3-1/2" Drill Pipe Elevators
AOT 8-5/8" Casing 65 Ton Side Latch Elevators
7" Casing Elevators
BJ 4-1/2" Casing Elevators
BJ 4-1/2" Casing Elevators with Capped Top for Snubbing Directional Drilling
BJ 3-1/2" Casing Elevators
2x Drill Collars 6" OD Spiral 30'+ Length 4" XH

BOPs:

9" 3M Townsend Annular
3 Station Closing Unit (1) Hydril K-40-1500 (1) Hydraulic Pump (1) 480 Volt Motor (1) Hydraulic Tank

RIG HOUSES:

26' 2001 Terry Camper, Bumper Hitch for Rig Manager
Dog House 10' x 30' Skid Load Dog House w/225 Bbl. Water Tank, Upper Dog House w/Knowledge Box, Light, Heater, Lowers into Water Tank, Lower Change out with 17 Lockers, Bench, Tool Board, Cabinet, 2 x 3 Wash Down Pump, Hydraulic Power unit for Pull Down Winches on Sub

MUD SYSTEM:

Mud Pit 200 Bbl. 3 Compartment w/(2) 4 x 3 Mission Centrifugal, Vortex VFSI Orbital 3000 Shaker, Caustic Barrel

UTILITY HOUSE/GENERATORS:

Caterpillar Generator Set Engine 3006 Ser# 9jNR 04985, Generator Model SR4B Ser. #8DR01144, Year 2001 15259 Hrs. Skid Load 8' x 28'

Fuel and Parts Trailer

2000 Gal Fuel Tank, Air Compressor, Accumulator Unit, Parts Shed 7-1/2 x 16' with Fire Cabinet, 8' x 42' Trailer

DRILL PIPE:

5800' (200 jts.) 4" 14# Grade X95 Range 2 DWB Drill Pipe w/ 4" FH Conn.
24 - 6" OD Spiral Drill Collars with 4-1/2" X-Hole Conn.

AUXILIARY EQUIPMENT:

Assorted Cross Over Subs
(4) Pipe Racks
Electric Trash Pump

Catwalk with Kohler Survey Machine, Hydraulic Power Unit and Pusher Cylinder to Place Drill Pipe to Floor

F1000 800 HP 450 GPM Triplex Pump w/6" Liners, 10" Stroke p/b Cat C-27 860 HP; 3668 Hrs - Since New - Mounted on 3 Axle XL Lowboy with Self Contained Elevating Gooseneck with 14' x 12' Parts Room with Locker, Shelves, Fire Cabinet, and Lights

Power Swivel Assembly

TDS 1330 SW Swivel, p/b Cat 3054C on 8' x 12' Skid Load 2422 Hrs. Since New

CAPABILITIES:

Hole Size 6-1/4 to 12-1/4
Depth with 4" Drill Pipe 5700
Casing 4-1/2 to 9-5/8 Range 3